Traffic Signals Ahead

Description: The Traffic Signals Ahead sign indicates that traffic control signals

are present in the Work Area.

Colour / Sheeting: Red, Yellow, Green & Black on Yellow, High Intensity



Stop Ahead

Description: The Stop Ahead sign indicates that a Stop sign is present in the

Work Area.

Colour / Sheeting: Red & Black on Yellow, High Intensity



Yield Ahead

Description: The Yield Ahead sign indicates that a Yield sign is present in the

Work Area.

Colour / Sheeting: Red, White, & Black on Yellow, High Intensity



Grooved Pavement

Description: The Grooved Pavement sign warns bicyclists and motorcyclists of

road surface conditions that require extra care and attention. This

sign is typically used where milling activities occur.

60 - 110 km/h 90 cm x 90 cm (#4551)

Colour / Sheeting: Black on Orange, High Intensity



Construction Zone Begins

Description: The Construction Zone Begins sign indicates that road users are

now entering the Construction Zone, where double fines for

speeding are enforceable.

Minimum Size:

120 cm x 90 cm (#4316)

Colour / Sheeting:

Black on Orange, High Intensity

CONSTRUCTION ZONE BEGINS

DÉBUT DE LA ZONE DE CONSTRUCTION

Construction Zone Ends

Description: The Construction Zone Ends sign indicates that road users have

reached the end of the Work Area and that roadway conditions have returned to normal. It also marks the end of where double

fines for speeding are enforceable.

Minimum Size:

120 cm x 90 cm (#4318)

Colour / Sheeting: Black on Orange, High Intensity

CONSTRUCTION ZONE ENDS

FIN DE LA ZONE DE CONSTRUCTION

Wet Paint

Description: The Wet Paint sign warns road users that line painting is occurring

ahead. It is to be mounted on the Trail Vehicle that follows the

paint truck.

Minimum Size:

120 cm x 90 cm (#4652)

Colour / Sheeting:

Black on Orange, High Intensity

Wet Paint
Peinture
Fraîche

Follow Me

Description: The Follow Me sign is used to advise road users that a Pilot

Vehicle will lead them through a Work Area and that the Pilot

Vehicle must be followed.

Minimum Size:

120 cm x 90 cm (#4654)

Colour / Sheeting:

Black on Orange, High Intensity

Follow Me Suivez-moi The mounting height varies depending on the sign size and the type of sign support. Figures 4-1 and 4-2 depict the proper sign position and mounting height for fixed and portable sign supports. Note: tabs are to be installed directly below the sign and shall not be installed on top or in front such that the sign is obscured. Signs should be mounted at a consistent height through the Work Area.




Figure 4-1: Sign Position and Height for Fixed Sign Supports




Figure 4-2: Sign Position and Height for Portable Sign Supports

Sequence

- Begin at the first advance warning sign on the same side of the road as the Activity Area.
- Proceed with the flow of traffic, placing all signs on the same side of the road as the Activity Area.
- Make a legal turn.
- Sign the opposite approach, beginning at the first advance warning sign and working with the flow of traffic.

Special Instructions

- Sign truck must display either 1) a Flashing Arrow Board set to the caution mode (recommended), or 2) a 360 degree amber light.
- A Trail Vehicle may be used based upon site specific conditions such as restricted sight distances or high traffic volumes.




Figure 4-3: Sign Setup (Two Lane Roads)

Sequence

- Ensure that all signs and Traffic Control Persons (TCPs) are in place.
- 2. Begin with the Transition Taper, laying out delineators with the flow of traffic.
- 3. Continue with the flow of traffic, laying out delineators in the Buffer and Activity Areas.
- 4. Lay out delineators in the termination taper.
- Install remaining traffic control devices such as traffic control signals, barricade boards, etc, if applicable.

Special Instructions

 Sign truck must display either 1) a FAB set to the caution mode (recommended), or 2) a 360 degree amber light.




Figure 4-4: Lane Closure Setup (Two Lane Roads)

Sequence 1. Ensure that all work activities are complete and that workers, materials, and equipment have been removed from the Activity Area. 2. Have TCPs regulate flow in both directions, as needed. 3. Pick up the delineators in the terminating taper (or at the furthest delineator if no termination taper exists). 4. Continue against the flow of traffic, picking up delineators in the Activity and Buffer Areas. 5. Have TCP #1 stop traffic in the closed lane. 6. Pick up delineators in the Transition Taper. **Special Instructions TCP #2** Sign truck must display either 1) a FAB set to Start Here the caution mode (recommended), or 2) a 360 degree amber light. Sign Truck Vacated Activity Area TCP #1

Figure 4-5: Lane Closure Removal (Two Lane Roads)

Sequence

- Ensure that the Activity Area is clear of all workers, materials, equipment, and Delineation Devices.
- Beginning on the same side of the road as the Activity Area, proceed with the flow of traffic, picking up all signs on the shoulder.
- 3. Make a legal turn.
- Pick up signs on the opposite approach, beginning at the first advance warning sign and working with the flow of traffic.
- 5. Make a legal turn.
- Pick up all remaining signs on the same side of the road as the Activity Area, beginning with the first advance warning sign and following the flow of traffic.

Special Instructions

- Sign truck must display either 1) a FAB set to the caution mode (recommended), or 2) a 360 degree amber light.
- A Trail Vehicle may be used based upon site specific conditions such as restricted sight distances or high traffic volumes.




Figure 4-6: Sign Removal (Two Lane Roads)

7 Typical Layouts for Two Lane Roads




- No signs are required for work that occurs outside 15 m from the edge of the travelled lane.
- No signs are required for work vehicles that are positioned off the shoulder area of the travelled lane onto private driveways for Very Short and Short Duration Work.
- No signs are required for mowing operations. However, the mower shall be equipped with a 360 degree amber light and a Slow Moving Vehicle Triangle.
- For mowing operations, the first swath adjacent to the road must be mowed following the direction of traffic.
- Shoulder must remain clear of all workers, vehicles, and equipment while work is in progress.

Roadside Work Any Duration All Volumes						
V 50 60-70 80-90 100						
s	50	75	100	150		


V - Existing Speed Limit (km/h)

S - Minimum Sign Spacing (m)



- Work Vehicle shall be equipped with a Flashing Arrow Board set to caution mode or a 360 degree amber light.
- 2. No workers, equipment, or vehicles shall encroach on the travelled lane.

Shoulder Work Very Short Duration (less than 30 min) All Volumes




Revised 2010

- Sign opposite approach in the same manner, without the Road Narrows sign.
- Construction Zone Ends sign to be placed directly across from Construction Zone Begins sign on the opposite approach.
- Continuous barrier may be replaced by flexible drums or delineator posts if anticipated work duration is 3 days or less.
- For work on bridge structures, a continuous Barrier is required for all Long Duration Work.

Shoulder Work Long Duration (greater than 1 day) **All Volumes** 50 60-70 80-90 100 1000 A 350 350 500 S 50 100 150 т 30 64 110 180 6/8 8/10 10 / 14 18 / 24 D В 50 75

- V Existing Speed Limit (km/h)
- A Advance Warning Distance (m)
- S Minimum Sign Spacing (m)
- T Taper Length (m)
- D Maximum Delineator Spacing in Taper/Tangent (m)
- B Buffer Area Length (m)



- Must maintain a minimum 2.5 m useable road width in the lane in which work is taking place.
- Sign opposite approach in the same manner, without the Road Narrows sign.
- Construction Zone Ends sign to be placed directly across from Construction Zone Begins sign on the opposite approach.
- For Very Short Duration Partial Lane Closures on roads with AADT ≤ 300 and Existing Speed Limit ≤ 50 km/h:
 - identified signs may be eliminated,
 - T maybe reduced to T/3,
 - Termination Taper may be reduced to two delineation devices.

	Partial Lane Closure Short Duration All Volumes					
٧	50	60-70	80-90	100		
Α	350	350	500	1000		
s	50	75	100	150		
т	30	64	110	180		
D	6/8	8 / 10	10 / 14	18 / 24		
$\overline{}$						

- V Existing Speed Limit (km/h)
- A Advance Warning Distance (m)

50

70


75

- S Minimum Sign Spacing (m)
- T Taper Length (m)

35

В

- D Maximum Delineator Spacing in Taper/Tangent (m)
- B Buffer Area Length (m)



NOTES: DETOUR 1. Sign other approach in the same S 2. All intersections along the Detour route shall display appropriate guide signs to clearly direct drivers along the intended path. ₿В 25 2S m 25 ONSTRUCTIO 4S m ROAD CLOSED TO THRU TRAFFIC **Rural Detour** ROUTE INTERDITE AU TRANSIT **Any Duration All Volumes** 60-70 80-90 100 DETOUR 300 300 500 1000 See S 50 75 100 150 NOTE #2 В 35 50 70 75 NORD V - Existing Speed Limit (km/h) A - Advance Warning Distance (m) S - Minimum Sign Spacing (m) B - Buffer Area Length (m) A m

- Sign opposite approach in the same manner.
- Construction Zone Ends sign to be placed directly across from Construction Zone Begins sign on the opposite approach.
- Buffer Vehicle with TMA only required when working on bridge structures.
- When working on bridges, the Activity Area shall be extended such that TCPs are not located on the structure.
- No passing sign is optional on roads with less than 300 vehicles per day.


equipped with TMA -See NOTE #3

Buffer Vehicle

Surveying (Lane Closure) Short Duration (greater than 30 min, less than 1 day) All Volumes

٧	50	60-70	80-90	100
Α	350	500	1000	1000
S	50	75	100	150
Т	30	64	110	180
С	30	40	50	50
D	6/8	8 / 10	10 / 14	18 / 24
В	35	50	70	75

- V Existing Speed Limit (km/h)
- A Advance Warning Distance (m)
- S Minimum Sign Spacing (m)
- T Taper Length (m)
- C Traffic Control Person Setback (m)
- D Maximum Delineator Spacing in Taper/Tangent (m)
- B Buffer Area Length (m)



- Sign opposite approach in the same manner.
- Construction Zone Ends sign to be placed directly across from Construction Zone Begins sign on the opposite approach.
- Traffic Control Person Ahead signs shall be positioned within 2S m to 3S m of the TCP at all times (shall be mounted on trail vehicle).
- The Activity Area shall not exceed 4 km.
- All work vehicles shall be equipped with 360 degree amber lights as a minimum.
- Trail vehicle not required on roads with a speed limit of 80 km/h or less.
- No passing sign is optional on roads with less than 300 vehicles per day.

CONSTRUCTION ZONE ENDS FIN DE LA ZONE DE CONSTRUCTION See NOTE #2 Work Maximum 1 km Vehicle(s) Sub-area Trail Vehicle (See NOTE #5) See NOTE #3 S/2 TAR GOUDRON S/2 Repeat every 1 km as work progresses S Α See NOTE #7 S NEXT/SUR S CONSTRUCTION ZONE BEGINS DÉBUT DE LA ZONE A m


Chip Sealing Short Duration (greater than 30 min, less than 1 day) All Volumes

Alli Tolulloo					
V	50	60-70	80-90	100	
Α	350	500	1000	1000	
s	50	75	100	150	
С	30	40	50	50	

- V Existing Speed Limit (km/h)
- A Advance Warning Distance (m)
- S Minimum Sign Spacing (m)
- C Traffic Control Person Setback (m)

 Both vehicles shall be equipped with a Flashing Arrow Board set to caution mode.


> Line Painting Moving Operation All Volumes



- No signs are required for work that occurs outside 15 m from the edge of the travelled lane.
- No signs are required for work vehicles that are positioned off the shoulder area of the travelled lane onto private driveways for Very Short and Short Duration Work.
- No signs are required for mowing operations. However, the mower shall be equipped with a 360 degree amber light and a Slow Moving Vehicle Triangle.
- For mowing operations, the first swath adjacent to the road must be mowed following the direction of traffic.
- Shoulder must remain clear of all workers, vehicles, and equipment while work is in progress.
- For work in the median, sign the other direction only if work is within 15 m of the opposing travel lane and no median barrier is present.


Roadside Work Any Duration All Volumes						
٧	50	60-70	80-90	100-110		
s	50	75	100	150		


- V Existing Speed Limit (km/h)
- S Minimum Sign Spacing (m)




- Work Vehicle shall be equipped with a Flashing Arrow Board set to caution mode or a 360 degree amber light.
- 2. No workers, equipment, or vehicles shall encroach on the travelled lane.
- 3. Use Figure 8-7 if insufficient shoulder width is available.

Shoulder Work Very Short Duration (less than 30 min) All Volumes








- Minimum lane width shall be at least
 5 m adjacent to the activity area.
- Advisory ramp speed shall be used for determining S, T, D and B values on the ramp. If no advisory is posted, use 60-70 km/h.
- Continuous barrier may be replaced by flexible drums or delineator posts if anticipated work duration is 3 days or less.
- Existing advisory ramp speed may be reduced where deemed necessary.

Barrier with 4:1 approach taper equipped with construction markers spaced at D (see NOTE #3)

Off Ramp (Partial Lane Closure) Short / Long Duration (greater than 30 min) All Volume

٧	50	60-70	80-90	100-110
Α	300	300	500	1000
s	50	75	100	150
Т	30	64	110	180
D	6/8	8 / 10	10 / 14	18 / 24
В	35	50	70	75

- V Existing Speed Limit (km/h)
- A Advance Warning Distance (m)
- S Minimum Sign Spacing (m)
- T Taper Length (m)
- D Maximum Delineator Spacing in Taper/Tangent (m)
- B Buffer Area Length (m)




- If the ramp is too short to provide distance "A", then Construction Ahead signs shall be placed on both approaches on the secondary road and display the appropriate directional arrows.
- Continuous barrier may be replaced by flexible drums or delineator posts if anticipated work duration is 3 days or less.
- Minimum lane width shall be at least
 m adjacent to the activity area.
- 4. If ramp speed is not posted, use 60-70 km/h for selecting A, S, T, D and B.

Barrier with 4:1 approach taper equipped with construction markers spaced at D (see NOTE #2)

On Ramp (Partial Lane Closure) Short / Long Duration (greater than 30 min) All Volumes

	All Volumos						
٧	50	60-70	80-90	100-110			
Α	300	300	500	1000			
S	50	75	100	150			
Т	30	64	110	180			
D	6/8	8 / 10	10 / 14	18 / 24			
В	35	50	70	75			

- V Existing Speed Limit (km/h)
- A Advance Warning Distance (m)
- S Minimum Sign Spacing (m)
- T Taper Length (m)
- D Maximum Delineator Spacing in Taper/Tangent (m)
- B Buffer Area Length (m)



- Paint Truck and Buffer Vehicle to display right arrow when working in the right lane travelled lane.
- 2. An additional trail vehicle may be utilized to control tracking.

Line Painting Moving Operation All Volumes

